

Appendix B

Detailed Project Scope Changes - Removals

Finished Grade Verification (OLS Survey) as per Fine Grade Verification Sheet
Supply and Install Electrical: Amphitheatre Lights
Supply and Install Beach Sand
Supply and Install Amphitheatre Structure Concrete Slab - Complete; in accordance with engineered drawings by Icon Shelter Systems Inc.
Contractor Coordination of Amphitheatre
Supply and Install Concrete Footings for Kite Structures; 2438mm dia concrete pedestal, F-2 exposure class, 25 MPa min., with reinforcing steel, at 1500mm deep including light sandblast finish
Contractor Coordination of Shade Sails
Supply and Install Double Swing Gate (Vehicular) - Complete including footings, concrete cylinder for metal pin, all required hardware and shop drawings
Supply and Install One (1) Secondary Washroom Building (5.5mx9m); - Complete in accordance with all Architectural, Structural, Mechanical & Electrical drawings and specifications (including shop drawings, commissioning and as-built drawings)
Contractor Coordination of Playground Equipment - Playground Area 2
Supply and Install Engineered Wood Fiber Safety Surface - Playground Area 2 including drainage layer, 100mm dia. perforated drainage pipe with all required connectors and connection to catch basins and geotextile as per manufacturers specifications; Also includes compacted granular base;.
Supply and Install Concrete Playground Area 2 Flush Curb (400mm Wide) including rebar reinforcing, light broom finish, and compacted granular base.
Supply and Install Concrete Accessible Ramp - Playground Area 2
Supply and Install 1.21m x 1.824m x 1.36m Canoe Dock Concrete Anchor - Complete; Concrete block to sit 0.15m above high-water level; Concrete block to be plumb, square and level including rebar and shop drawings - refer to details
Fine Grade Verification (OLS Survey) as per Fine Grade Verification Sheet
Reduction of 25% to Softscape Planting Material
Supply and Install One (1) Custom 30' x 40' Custom Amphitheatre by Icon Shelter Systems Inc. (Quote no. TBV40x30); Four (4) - 8"x8" square columns, Mega Rib Panel Roof Top; Tongur and Groove cedar ceiling on interior roof, electrical cutouts in columns for lighting, Concrete Slab design, stamped engineer drawings and post install inspection and engineer review letter. Includes installation and freight

Finished Grade Verification (OLS Survey) as per Fine Grade Verification Sheet	
Supply and Install (1) One Shade Sail - Kite Structure combination by ABC Recreations (Quote no. 19-5271-A-R1); One (1) 16' Kite Tension Shade Shelter (IKTE-16), One (1) 14' Kite Tension Shade Shelter (IKTE-14), One (1) 12' Kite Tension Shade Shelter (IKTE-12) including Hilti Epoxy Anchor Bolts, stamped Engineer Drawings, Engineered Footing Design and Post Installation Inspection and Shipping	
Playground Equipment by Kompan Supplied and Installed by Open Space Solutions Inc. Quote no:191210-2-R1, Drawing no.: Bobcaygeon Beach Park 102219 Including CSA certification after installation	
Supply and Install Docking Systems Complete by Poralu Marine (or approved equal) including Fixed Boardwalks, Anchoring Systems, Ramps, and Accesses, LED Lighting, Decking, Freight, Delivery and Turnkey Installations. Quote no. 20200309 Rev 0.	
Total Miscellaneous Items	\$947,955
Supply and Install One (1) Rental Building (7mx9m) - Complete in accordance with all Architectural, Structural, Mechanical & Electrical drawings and specifications (including shop drawings, commissioning and as-built drawings)	
Supply and Install Artificial Turf (Non Play Areas) nailor board fastened to concrete curb, drainage layer, 100mm dia. perforated drainage pipe with all required connectors and connection to catch basins and geotextile as per manufacturers specifications; Also includes compacted granular base;.	
Supply and Install Concrete Artificial Turf Barrier Curb, 200mm Wide (Non Play Area) including compacted granular base	
Supply and Install Artificial Turf Safety Surface including Turf Cushion Layer (Playground Area 2), nailor board fastened to concrete curb, drainage layer, 100mm dia. perforated drainage pipe with all required connectors and connection to catch basins and geotextile as per manufacturers specifications; Also includes compacted granular base;.	
Supply and Install Two (2) Shade Sail - Kite Structures by ABC Recreations (Quote no. 19-5271-A-R1); Two (2) 16' Kite Tension Shade Shelter (IKTE-16), Two (2) 14' Kite Tension Shade Shelter (IKTE-14), Two (2) 12' Kite Tension Shade Shelter (IKTE-12) including Hilti Epoxy Anchor Bolts, stamped Engineer Drawings, Engineered Footing Design and Post Installation Inspection and Shipping	
Supply and Install Concrete Footings for Kite Structures; 2438mm dia concrete pedestal, F-2 exposure class, 25 MPa min., with reinforcing steel, at 1500mm deep	

Finished Grade Verification (OLS Survey) as per Fine Grade Verification Sheet	
Supply and Install Two (2) BL229 - Rising Barrier Gate - Left, round arm 19'8" (6.0m) with standard tip support and analog sensor. Includes Double Channel Loop Detector; Heating - UL Forced Fan Heater (400W) for BL229; Detection Loop in PVC - 3'11" x 7'10" x 32'10" (1.2 x 2.4 x 10m); ParkNet Multi-Services Terminal, Includes Coin Receiver, 2D ticket reader, 4G Modem and Antenna, relays and misc. hardware; Inbuilt debit-credit card reader, model UX400, Chip, PIN and Contactless reader; 4G Modem and Cloud based management software; Miscellaneous Materials; Shipping; Installation, Program, Test and Commission (including all electrical requirements)	
Supply and Install Concrete Footings for Vehicular Gates; 914mm dia concrete pier, 35 Mpa min. with reinforcing steel at 1200mm deep	
Supply and Install Standard Concrete Paving with light Broom Finish including compacted granular base around perimeter of Rental building	
Supply and Install West CIP Concrete Entry Sign Wall; including Sandblasted Lettering Painted Black, shadow-line and rebar reinforcement.	
Supply and Install East Concrete Entry Sign Wall; including Sandblasted Lettering Painted Black, shadow-line and rebar reinforcement.	
Supply and Install Accessible Beach Water Carpet	
Total Provisional Items	\$655,436